



“STRUCTURAL DESIGN, COMPARATIVE STUDY OF RCC BUILDING ON PT SLAB & FLAT SLAB BUILDING UNDER THE DYNAMIC ANALYSIS”

¹ Omkar Burde, ² Vishwajeet Kadlag,

¹PG Student, Department of Civil Engineering Dr. D Y Patil School of Engineering and Technology, Charholi (BK), Pune-412 105, Maharashtra, India,

²Associate Professor, Dept. of Civil Engineering, Dr. D Y Patil School of Engineering and Technology, Charholi (BK), Pune-412 105 Pune, Maharashtra, India,

Abstract : In this study we have carried out detailed study of various concepts of precast, go through number of Literature & found the facts associated with it. Existing reinforced concrete Structures stock is wide and also includes buildings with precast elements, being largely used since Fifties primarily to satisfy needs of the manufacture and tertiary purposes. Their diffusion has been supported by flexibility of structural net dimensions and by the economy and efficiency of the constructional process. For this purpose, a reference project at Chennai location is taken and modelled in SAP2000 software to analyses the structure and design.

Key Words: Design, Dynamic Analysis, PT Slab, Flat Slab, Prefabricated Structure, SAP2000

I. INTRODUCTION

INTRODUCTION

Mechanically attaching structural components uses bolts, welds, anchors, reinforcing steel, grout, and concrete. Structure connections must strengthen structural integrity. They transfer forces between system components to provide structural interaction. Researchers studied PCC beam-column junction load distribution and behavior. Connection type affects constructability, stability, strength, flexibility, and residual forces. PCC member connections are built for different loads. Researchers can analyze and generate accurate connections under different loads.

Precast concrete is fast and high-quality. Precast concrete is used to build car parks, commercial, cultural, hotels, dorms, apartment complexes, bridges, and industrial buildings. Beam-to-column connections govern precast concrete structures' structural performance. In prior earthquakes, faulty design, detailing, and manufacturing of the joints devastated precast concrete structures. Researchers believe weak connections are the main cause of earthquake damage.

Massive wall and floor concrete panels are linked vertically and horizontally to create room areas. A bond-like panels; panels resist gravity. Precast frames can be made with linear parts or beam- column sub-assemblages. Connecting faces between precast beam- column sub-assemblages can be far from crucial frame areas.

however linear elements are often preferred due to the difficulty of producing, handling, and erecting spatial parts. Shear walls withstand lateral loads, while slab-column structure resists gravity loads. This category includes two systems: Load-bearing columns and slabs are prefabricated in a lift slab system with walls. Two floors tall; precast structural parts have special joints. Slab-column pre-stressed Continuous horizontal pre- stressing in two orthogonal directions to-3-story precast columns. The column spans are reinforced concrete. Precast System Type

Precast systems are classified according to the load bearing structure:

- Frame systems
- Slab column systems with wall
- System mix
- Precast Slabs
- Precast Beams and Girders
- Precast Columns
- Precast Walls
- Precast Stairs

Initially, precast parts are all designed and sized similarly. All floors' slab designs and drawings should be similar. Beams, columns, stairways, and railway sleepers are similar. Initial investment is needed for structure. If a factory makes several similar parts, the investment is less. The government should provide affordable land so the initial cost of building the pre-cast factory is lowered and

the owner makes a profit, boosting the country's economy. Commercial and public sectors should organize workshops or training programs to train individuals or labor to solve difficulties arising from an untrained workforce for various phases of the activity. Good road access; site space Less traffic before building begins, site layout must be finalized. It should be well-planned and have enough space to store erected pieces. Plan the site layout. Light concrete is used to lighten precast parts. New approaches and technologies have boosted the construction industry. Precast concrete is a cost-effective, quality-controlled procedure used in several nations. The safe, productive, and excellent environment; design and planning must be linked to improve and speed up building.

2. METHODOLOGY

- Building design using Static Linear Analysis.
- Dynamic analysis using SAP2000 software
- Study of prefabricated structure and all parameters
- 1) Story drift
- 2) Story acceleration
- 3) Overturning Moment
- 4) Story displacements
- 5) Axial force
- 6) Base shear
- Analysis result
- Result and discussion
- Conclusion

DESIGN AND MODELLING

- Material properties
- M40 FE500
- Beam 300x600, beam 350x675mm
- Col 500x500
- Col 450x450
- Study for literature review survey to study the construction techniques of precast and traditional method we have gone through

various research papers, books, and some field works

- Building design using Static Linear Analysis.
- Building plan using AutoCAD
- Dynamic analysis using SAP 2000 software
- Study of prefabricated structure and all parameters
- 1. Base Reaction
- 2. Base vertical Reaction
- 3. Time Period
- 4. Base shear

Material Properties and Load

- Grade of concrete M-40
- Grade of steel Fe500
- Load pattern
- Method of analysis - non-linear static analysis (response spectrum analysis)
- Dead load
- Live load
- Super dead load
- Earthquake x dire (IS 1893:2002)
- Earthquake y dire (IS 1893:2002)
- Seismic Zone = Zone - III
- Wind Zone = Zone - V

For regular Structure

- Frame properties
- Beam 250mm x 450mm
- Column 250X 500mm
- Slab thick 150mm

For Flat Slab

- Col 400mm X 400mm
- Slab 250mm

PT slab model

- Tendon dia 300mm
- Beam 250mm x 450mm
- Column 250X 500mm
- Slab thick 150mm

Load Combinations

- 1.2DL+1.6LL
- 1.2DL+LL+EQ_{x/y}
- 1.2DL+LL-EQ_{x/y}
- 1.2DL+LL+EQ_{x/y}
- 1.2DL+LL-EQ_{x/y}
- 0.9DL+EQ_{x/y}
- 0.9DL-EQ_{x/y}
- 1.2DL+LL+R_{sx/y}
- 1.2DL+LL-R_{sx/y}
- 0.9DL+R_{sx/y}
- 0.9DL-R_{sx/y}

IV. RESULTS AND DISCUSSION**1. Building Analyses****Table1: Base Shear for RCC, Flat, and PT**

	BASE SHEAR	(KN)	
TYPE	RCC	FLAT	PT
G+7	496.0	391.2	549.6
G+14	466.5	366.0	621.6
G+21	631.6	356.0	962.2

Table2: Base Reaction

	BASE SHEAR	(KN)	
TYPE	RCC	FLAT	PT
G+7	10377.7	5427.0	14589.7
G+14	20755	10033.7	32973.6
G+21	46295	17852.2	71451.9

The maximum base reaction for PT slab continuously increasing for G+7, G+14 and G+21 in the three models it can show the above graph. The base reaction is around 44% increases as compare to the RCC slab structure. And the 70% increases as compared to Flat slab structure.

Table3 Time period (Sec)			
TYPE	RCC	FLAT	PT
G+7	1.52	1.33	1.74
G+14	3.25	2.65	3.52
G+21	4.17	4.17	5.28

The time period is increases for the PT slab structure as compared to the RCC slab and Flat slab is shown in the above graph.

Table 4 Maximum Vertical Reaction**Table 4 Maximum Vertical Reaction**

TYPE	RCC	FLAT	PT
G+7	904.81	698.61	1246.25
G+14	1648.85	1143.96	2629.78
G+21	2515.23	2098.56	4039.65

The above graph shows that the maximum vertical reaction (KN) for PT slab is increases for all G+7, G+14 and G+21 it almost 35% and 70% as compare to RCC slab and Flat slab structure.

II. CONCLUSIONS

- The above graph shows that the maximum vertical reaction (KN) for PT slab is increases for all G+7, G+14 and G+21 it almost 35% and 70% as compare to RCC slab and Flat slab structure.
- The maximum base reaction for PT slab continuously increasing for G+7, G+14 and G+21 in the three model it can show the above graph. The base reaction is around 44% increases as compare to the RCC slab structure. And the 70%increases as compared to Flat slab structure.
- The Dead load of PT slab structure is increased by 20% and 38% as compared to RCC and Flat slab structure.
- As a result, because the concrete required and the cost of steel required are substantially lower in the case of PT slab construction than in the case of R.C.C, Flat Slab construction, it is more economical to construct the structure evaluated with PT Slab than with R.C.C and Flat Slab
- The time period will be maximum at mode 1, 2 and 3. After mode 3, time period will reduce drastically.
- Flat slab structures are the best solution for high rise structure as compared to conventional slab structure. And post tension slab

REFERENCES

- [1] Vakas K. Rahman, prof. A.R.Mundhada," Vol 3 issue 3 may 2013 (IJMER)", "Comparative study of RCC and prestressed concrete slab".
- [2] Lovneesh Sharma Nileshwar Taak, Pankaj Mishra "A Comparative study between the pre-engineered structures and conventional structures using STAADPRO", March 202, DOI:10.1016/j.matpr.2020.12.942,
- [3] Jasim Anamangadan, J. Visuvasam, Anoj Kumar Dubey, "Comparative Study on Various Behaviours of an RC Structure with Pre-stressed Concrete Structure", January 2019, DOI:10.1007/978-981-10-8016-6_27,
- [4] Hari Prasad M "Comparative Study between Precast and Cast In-Situ Structure Under Combination of Dynamic Loads and Connections between Precast Elements", IJSRD - International Journal for Scientific Research & Development [Vol. 4, Issue 04, 2016 | ISSN (online): 2321-0613
- [5] Akash Lanke, Dr.D.Venkateswarlu,"Vol 3 issue 6 june 2016 (IRJET)", "Design, cost & time analysis of precast & RCC building"
- [6] Sukhi V. Sendanayake David P. Thambiratnam Nimal Perera "Seismic mitigation of steel modular building structures through innovative inter-modular connections", Elsevier, 25 October 2019
- [7] Bhanu Prakash P.M, Dr. Vijaya Kumar Y.M and T A Srirama Rao "Review On Comparative Study On RCC And Steel Structure For Different Criteria's," ISSN:2277-7881; Impact Factor: 6.514(2021); IC Value: 5.16; ISI Value:2.286, International Journal of Multi-disiplinary Educational Research
- [8] Nagaraju Kaja, Anupam Jauswal "Review of Precast Concrete Technology in India," International Journal of Engineering Research & Technology (IJERT) <http://www.ijert.org> ISSN: 2278-0181 Published by : www.ijert.org Vol. 10 Issue 06, June-2021
- [9] Umamaheswara Rao Tallapalem, Shaik Nurulla, Srinivasarao Vallu, "Time History Analysis on Precast Building Connections" International Journal of Recent Technology and Engineering (IJRTE) ISSN: 2277-3878, Volume-8 Issue-4, November 2019
- [10] P. K. Aninthaneni and R. P. Dhakal, Conceptual development: low Loss Precast Concrete Frame Building System with Steel Connections, 2014 NZSEE Conference, New Zealand, 2014.