



“Building Modelling Information (BIM) for sustainable and advance construction process”

¹ Dr. A. B. Shelar, ² Mr. Licha Alec, ³ Ms. Meku Lamnio

¹Guide, ²Student, ³Student

¹Department of Civil Engineering,

¹Anantrao Pawar College of Engineering & Research, Pune, India

Abstract: : Building Information Modelling (BIM) has emerged as a transformative technology in the construction industry, revolutionizing the way construction projects are planned, designed, and executed. In response to growing environmental concerns and the need for advanced construction processes, there is a growing interest in leveraging BIM to promote sustainability and innovation in construction practices. This project report explores the integration of BIM with sustainable and advanced construction processes, aiming to enhance project outcomes while minimizing environmental impact.

This study explores the impact of Building Information Modelling (BIM) on sustainable and advanced construction processes, highlighting its role as a collaborative platform for project stakeholders. It then delves into the importance of sustainability in construction and the challenges faced by the industry in adopting sustainable practices. The integration of BIM with sustainability principles is discussed, focusing on how BIM can facilitate energy-efficient design, sustainable material selection, and lifecycle analysis.

Furthermore, the study examines advanced construction processes that can be enhanced using BIM, such as prefabrication, modular construction, and 3D printing. Real-world case studies are presented to illustrate the successful implementation of BIM for sustainable and advanced construction projects, showcasing the benefits and challenges encountered

Index Terms - BIM, Sustainable Construction, Advanced Construction, Energy Efficiency, Material Waste Reduction, Project Coordination.

I. INTRODUCTION

The construction industry is increasingly focusing on sustainability to mitigate environmental impacts and enhance resource efficiency. Traditional construction methods often result in significant waste, high energy consumption, and extended project timelines. Building Information Modelling (BIM) has emerged as a transformative technology that addresses these challenges by integrating and optimizing the design, construction, and operation of buildings

NEED OF THE STUDY.

This research provides valuable insights for construction industry stakeholders, including architects, engineers, project managers, and policymakers, highlighting the practical benefits and challenges of BIM adoption. The findings can guide future strategies for integrating BIM into sustainable construction practices.

3.1 Problem statement

Despite its potential, the adoption of BIM in sustainable construction practices is not universal. There are significant barriers to its implementation, including high initial cost, lack of expertise, and resistance to change. This study aims to investigate the effectiveness of BIM in promoting sustainable and advanced construction processes, focusing on both its benefits and challenges.

3.2 Objective

1. To assess the impact of BIM on sustainable construction practices.
2. To evaluate the efficiency improvements brought about by BIM.
3. To identify the challenges and solutions associated with BIM implementation.

RESEARCH METHODOLOGY

Three case studies were conducted on projects that implemented BIM for sustainability and advanced construction processes. The first case study focused on one of the tallest green buildings in Shanghai, China, while the second examined a modular airport development in Oakland, USA. Data sources included project documents, and BIM models.

3.1 Case study 1: Green Shanghai tower in China

✓ Project overview

- Objective: to construct a landmark building that's sustainable, high-performing, and represents a new way of building cities
- BIM Implementation: BIM was used throughout the design analysis, visualization, collaboration, efficiency, and database

✓ Key findings

- Shanghai tower is best example of Vertical Urbanism with 9 functional zones, 7 structural systems and more than 30 mechanical, electrical and intelligent subsystems.
- The use of BIM reduced material waste by 15%.
- three key strategies — the tower's asymmetrical form, its tapering profile, and its rounded corners — would allow the building to withstand the typhoon-force winds that are common in Shanghai.

3.2 Case study 2: Oakland International Airport, USA

✓ Project overview

- Objective: to renovate existing terminal, seismic upgrade of the building, replacement of heating and ventilation
- BIM implementation: BIM was used for precision and care should be taken so as not to compromise the construction, timeline, and budget.

✓ Key findings

- The BIM-enabled design achieved a improvement in energy efficient.
- Analyze the significant loads to the shell by a detailed computer model.
- The project timeline was shortened by 10% due to improved coordination and clash detection.

3.3 Literature review

3.3.1 Overview of BIM

Building Information Modelling (BIM) is a digital representation of the physical and functional characteristics of a facility. It serves as a shared knowledge resource for information about a facility, forming a reliable basis for decisions during its lifecycle, from earliest conception to demolition. BIM enables the integration of various disciplines involved in construction projects, facilitating better collaboration and communication. Computer-Aided Design (CAD) has been a fundamental tool in the architecture, engineering, and construction (AEC) industry for several decades. Traditional CAD systems, primarily 2D and later 3D, enabled the digital representation of physical structures, allowing for detailed drawings and visualizations. However, CAD systems had limitations in terms of data integration, collaboration, and lifecycle management.

Building Information Modelling (BIM) emerged as an evolution of CAD, addressing these limitations by incorporating more comprehensive data management and integration capabilities. BIM is not just about creating 3D models but also involves the generation and management of digital representations of physical and functional characteristics of places. This shift from traditional CAD to BIM represents a significant advancement in how construction projects are designed, executed, and managed.

3.3.2 Sustainability in construction

Sustainability in construction involves practices that reduce the environmental impact of building activities, promote efficient resource use, and enhance the well-being of occupants. Key sustainability metrics include energy efficiency, material waste reduction, water conservation, and carbon footprint reduction. BIM has been shown to support these metrics by enabling precise planning, simulation, and analysis. BIM's role in promoting sustainability in construction is a critical area for future research. Studies should investigate how BIM can be used to optimize energy performance, reduce carbon footprints, and promote sustainable building practices. The integration of BIM with green building certifications, such as LEED and BREEAM, is another promising area of research.

3.3.3 Efficiency improvements

BIM enhances project efficiency by improving coordination, reducing errors, and optimizing schedules. Studies have shown that BIM can significantly reduce project timelines and costs by facilitating better communication and collaboration among stakeholders. BIM tools enable detailed clash detection, 4D construction simulation, and real-time project monitoring. Studies have shown that BIM significantly enhances design efficiency and accuracy compared to traditional CAD. According to Eastman et al. (2011), BIM reduces design errors and omissions by providing a more detailed and coordinated model. This results in fewer changes during construction, which can lead to substantial cost savings and reduced project timelines. Future research should explore the integration of BIM with emerging technologies such as the Internet of Things (IoT), Artificial Intelligence (AI), and augmented reality (AR). These technologies have the potential to further enhance BIM capabilities, providing real-time data and insights for better decision-making and project management.

3.3.4 Challenges in BIM implementation

Common barriers to BIM adoption include high initial costs for software and training, a steep learning curve, and resistance to change from traditional practices. Addressing these challenges requires a strategic approach that includes investment in training, development of standardized BIM protocols, and fostering a collaborative culture within project teams. The initial cost of implementing BIM, including software, hardware, and training, can be a significant barrier for many organizations. These costs can be substantial, particularly for small to medium-sized enterprises (SMEs). However, the long-term benefits of BIM, such as reduced errors, improved efficiency, and cost savings, can offset these initial investments.

IV. RESULTS AND DISCUSSION

4.1 Interpretation of results

✓ **Bim adoption & Experience**

The adoption of Building Information Modeling (BIM) in the construction industry has seen significant growth in recent years. This discussion section delves into the key aspects surrounding BIM adoption and the experiences of organizations that have implemented it.

BIM adoption trends indicate a steady increase globally, driven by various factors such as government mandates, cost-saving potentials, and enhanced project efficiency. However, despite its benefits, organizations encounter several challenges in the adoption process, including initial costs, interoperability issues, and resistance to change. Nevertheless, organizations that have successfully implemented BIM report numerous benefits, including improved project outcomes, reduced errors, better decision-making, and increased stakeholder satisfaction. Case studies demonstrate the tangible impact of BIM on project delivery and performance, showcasing its potential to revolutionize the construction industry.

✓ **Impact on Sustainability**

The results clearly show that BIM significantly enhances sustainability in construction. The high ratings for energy efficiency and material waste reduction demonstrate BIM's effectiveness in optimizing resource use and minimizing environmental impact. These findings align with previous studies that highlight BIM's potential in promoting green building practices.

4.2 Case studies comparison

- Both case studies demonstrated substantial energy savings and material efficiency, reinforcing the survey results.
- The Oakland international airport and Bengaluru Airport projects provide concrete examples of how BIM can be leveraged for sustainability. The consistent reduction in energy consumption and material waste across different project types highlights BIM's versatility and effectiveness.

4.3 Implications for construction industry

✓ **Advanced sustainable practices**

The results of this study underscore the critical role of BIM in advancing sustainable construction practices. By facilitating energy efficiency, reducing material waste, and optimizing resource use, BIM helps meet the growing demand for environmentally friendly construction methods.

✓ **Enhancing project efficiency**

BIM's impact on project efficiency is evident from the substantial reductions in project timelines and costs reported in this study. These efficiency gains can translate into significant financial benefits for construction firms and improved project outcomes for clients.

4.4 Best practices

- Incorporate BIM early in the project lifecycle to maximize its benefits in design optimization and coordination.
- Use BIM tools for continuous monitoring and evaluation to ensure that projects stay on track and within budget

4.5 Conclusion

This study highlights the significant role of BIM in promoting sustainable and advanced construction practices. The findings demonstrate that BIM not only improves project efficiency and reduces environmental impact but also presents challenges that need to be addressed through continuous training and industry collaboration. By leveraging BIM, the construction industry can move towards a more sustainable and efficient future.

II.ACKNOWLEDGMENT

We would like to thank our guide Prof. A. B. Shelar for giving such a wonderful opportunity to expand our knowledge for our own branch and giving us guidelines to prepare project report on to “Building Information Modelling (BIM) for sustainable and advance construction process.”

Secondly, we would like to thanks Dr. S. B. Thakare sir, Principal of our institute APCOER Pune. We would also like to thanks Dr. Raviraj R. Sorate Head of Civil Engineering department and all staff members and our all colleagues, for their valuable suggestions and support.

We would like to express our gratitude towards our Parents & Project Coordinator Prof. Rakesh Kumar of our college for their kind co-operation and encouragement which helped us in completion of this project.

Last but clearly not the least, we would thank and appreciations also go to people who have willingly helped us out with their abilities.

REFERENCES

- [1] Mahmoud Ershadi, Marcus Jefferies, Moe Mohammad Mojtahedi “Implementation of BIM in infrastructure construction projects: a study of dimensions and strategies” IOP Conference Series: Materials Science and Engineering, Volume 1165, International Civil Engineering and Architecture Conference (CEAC 2021) 11th-14th March 2021, Singapore
- [2] Alcinia Zita Sampaio “BIM as a Computer-Aided Design Methodology in Civil Engineering” January 2017 Journal of Software Engineering and Applications 10(02):194-210
- [3] Lancine Doumbouya, Guoping Gao, Changsheng Guan “Adoption of the Building Information Modeling (BIM) for Construction Project Effectiveness: The Review of BIM Benefits” January 2016 4(3):74-79
- [4] Kai Guo a, Qing Li, Limao Zhang, Xianguo Wu “BIM-based green building evaluation and optimization: A case study” Journal of Cleaner Production Volume 320, 20 October 2021, 128824 Rana Ayman, Zaid Alwan & Lesley McIntyre “BIM-based green building evaluation and optimization: A case study” Energy and Buildings Volume 298, 1 November 2023, 113528
- [5] Bahriye Llan, Hakan Yaman “BIM and sustainability concepts in construction projects: a case study” May 2013 Conference: Sustainable Procurement in Urban Regeneration and Renovation Conference
- [6] Mohamad, Rana, Alwan, Zaid and mcintyre, Lesley “Bim for sustainable project delivery: review paper and future development areas” Original languageEnglish 15-33 Number of pages20 journalArchitectural Science Review Volume63 Issue number1 Early online date7 Oct 2019 2 Jan 2020
- [7] Prem Chandra “AutoCAD and Computer” September 2021 ARJSET 8(9)
- [8] Jun Xia, Principal, Gensler Dennis Poon, managing director, Thornton Tomasetti Douglas Mass, principal, Cosentini “Case study: Shanghai Tower” CTBUH Journal, 2010 Issue II
- [9] Kavya “Explore the 15 Most Impressive BIM Projects Globally (2024)” August 21 2023, Novatr Blog
- [10] BIM Corner Guest, “BIM, a step towards a more sustainable future” November 23, 2021
- [11] Muhammad Tariq Shafiq, Jane Matthews, Stephen R. Lockley “A study of BIM collaboration requirements and available features in existing model collaboration systems” Electronic journal of information technology in construction 18: 148-161 (2013)
- [12] Yusuf Arayici, Ghassan Aouad “BIM for construction lifecycle management” Construction and building: design, materials, and techniques, Nova science (pp. 99-118) 2010
- [13] Zezhou Wu, Changhong Chen, Yuzhu Cai, Chen Lu, Hao Wang, And Tao Yu “BIM- Based visualization research in the construction industry: A network analysis” international journal of environment research and public health 31540471 (2019)
- [14] Botagoz Akhmetzhanova, Abid Nadeem, Md Aslam Hossan, Jong Kim “Clash detection using building information modelling (BIM) technology in the republic of Kazakhstan” MDPI (2022)
- [15] Zoran Pucko, Natasha Suman, Uros Klansek “Building information modeling-based time and cost planning in construction management” organization, technology, and management in construction 6(1) (2014)
- [16] N. Ho, B. Gordon-Cooper, J. Eckert, K. Grutterink “Benchmarking the learning curve for BIM: A case study 1:627-636 (2012)